


Prefabricated Bonding Assembly – LPP692



- Prefabricated assembly includes rebar with an exothermic weld to copper conductor
- Wire tie or weld rebar to construction steel before pouring concrete and route conductor pigtail to down lead or ground lead location



| | |
|-----------------------------|-----------------|
| Part Number | LPP692 |
| Material | Copper Steel |
| Conductor Type | LPC126R |
| Pigtail Length | 5' |
| Rebar Size, US | #4 |
| Length (L) | 18" |
| Unit Weight | 2.935 lb |
| Standard Packaging Quantity | 1 pc |
| UPC | 78285643372 |

WARNING

nVent products shall be installed and used only as indicated in nVent's product instruction sheets and training materials. Instruction sheets are available at www.erico.com and from your nVent customer service representative. Improper installation, misuse, misapplication or other failure to completely follow nVent's instructions and warnings may cause product malfunction, property damage, serious bodily injury and death and/or void your warranty.

© 2020 nVent All rights reserved

nVent, nVent CADDY, nVent ERICO, nVent ERIFLEX and nVent LENTON are owned by nVent or its global affiliates.

All other trademarks are the property of their respective owners. nVent reserves the right to change specifications without prior notice.